**BOB Agent Setup** Kuppam Solar Site Setup in progress

● 3 systems connected All changes saved

7 of 7 configuration decisions completed · 3 activation scenarios passed

**Configuration ready for activation safety review** 7 of 7 settings complete · 3 required scenarios passed

| | |
|---|---|
| Objective | Maintain supply reliability |
| Asset | Battery 1 |
| Trigger | Demand gap >3 MW for 5 min |
| Max discharge | 6 MW |
| Max duration | 30 min |
| Min reserve | 55% |
| Automation | Automatic within limits |
| Recovery | Battery 1 unavailable → grid-import approval request |
| Notifications | In-app and email |
| Approval floor | Immutable 30 min |

## Choose a situation to see how BOB will respond

Testing uses simulated data and will not control live equipment.

**Current site conditions** Passed
Test how BOB responds to the current 6 MW demand gap
Solar: 38 MW Demand: 44 MW Battery: 72%

**Battery unavailable** Passed
Recovery passed: Battery 1 unavailable → grid-import approval requested

**Low battery charge** Not tested
Test whether BOB protects the configured battery reserve
Battery: 58% Reserve: 55%

**High battery temperature** Passed
Safety blocking passed: discharge blocked at 47°C
Temp: 47°C Max: 45°C

**Higher site demand** Passed
Approval required above 6 MW · reserve protected
Solar: 38 MW Demand: 52 MW Gap: 14 MW

**Delayed battery data** Passed
Delayed data passed: action blocked after 2 min delay
Delay: 2 min

### Test scenario: Current site conditions

Selected AI — Simulation 2026-01-18 14:32:18

SOLAR GENERATION 38 MW FORECAST → SITE DEMAND 44 MW FORECAST → DEMAND GAP 6 MW

BATTERY 1
72% · Available · Max 8 MW · Reserve 55%

GAP FORECAST
Continues ~20 min · With

● Simulation completed — 6 checks in 4 seconds AI — Simulation

**BOB can safely execute this action within configured limits**
Automatic discharge up to 6 MW · Approval required above 6 MW · Reserve protected above 55% · Immutable floor 30 min

In this scenario, BOB can discharge Battery 1 within the configured automatic limits. Safety blocking and recovery scenarios also passed, confirming that discharge is blocked when Battery 1 is unavailable or temperature exceeds 45°C and that grid-import approval is requested when Battery 1 cannot support the gap.

### When will BOB act?

- ● Demand exceeds solar by >3 MW
- ● Gap continues for 5 min · Within immutable 30 min floor
- ● Battery charge above configured reserve of 55%
- ● Gap forecast to continue 15+ min · Within 30 min limit
- ● Battery 1 available and temperature below 45°C
- ● Live battery data available and no critical warning
- ● No critical battery warning and no delayed data

In this test, demand is 6 MW above solar and all trigger conditions are met.

### What will BOB do?

AI — Planned action

1. Start discharging Battery 1 at 6 MW · Within configured automatic limit
2. Cover the 6 MW demand gap with battery energy · Reserve stays above 55%
3. Monitor battery charge, temperature, and live data every 15 seconds
4. Continue until demand normalizes, reserve reaches 55%, temperature exceeds 45°C, or 30 min limit is reached
5. Record action and notify configured users via in-app and email

### How will the action progress?

NOW
Solar 38 MW · Demand 44 MW · Gap 6 MW · Battery 72% · Temp 42°C

AFTER 5 MIN
Trigger confirmed · Battery verified · Safety checked · Reserve above 55% · Temp below 45°C

ACTION STARTS
Battery 1 discharges at 6 MW · Demand fully supplied · No grid import · Reserve stays above 55%

DURING EXECUTION
Charge, temp, and live data monitored every 15s · Demand and solar observed

AFTER ~15 MIN
Battery drops from 72% to ~64% · Demand fully supplied · Reserve stays above 55%

ACTION ENDS WHEN
Demand normalizes · Battery reaches 55% · 30-min limit · Temp exceeds 45°C · Health warning · Data unavailable

### How will energy flow?

BEFORE

Solar 38 MW → Demand 44 MW → Gap 6 MW Grid import risk

DURING

Solar 38 MW + Battery 6 MW = 44 MW → Demand 44 MW → Gap 0 MW Grid 0 MW

### What protects the battery and site?

| WILL NOT EXCEED | WILL STOP IF |
|---|---|
| Max discharge 6 MW | Battery reaches 55% |
| Max duration 30 min | Temp >45°C |
| Max energy 3 MWh | Health warning raised |
| Min reserve 55% | Data unavailable |
| Immutable floor 30 min | Demand normalizes |
| | Battery rejects command |
| | 30 min limit reached |

BOB cannot continue if any safety condition is no longer satisfied.

### Is approval required?

● **No approval is required for this 6 MW discharge**

6 MW discharge is within the configured automatic limit
Duration within immutable 30-minute floor
Battery stays above configured 55% reserve
Confidence above 85% · AI simulation
No grid import needed for this 6 MW discharge
Battery health: Normal · Safety blocking and recovery scenarios passed

### What is the expected result?

AI — Predictions AI — Predictions 93% confidence

| | |
|---|---|
| Demand | Fully supplied · No grid import |
| Battery after | ~64% · Reserve above 55% |
| Grid import | Not required for this 6 MW discharge |
| Cost avoided | ₹4,800 · AI estimate |
| Critical interruption | None · Safety blocking and recovery scenarios passed |
| Reserve | Protected above configured 55% |
| Duration | ~15 min · Within immutable 30 min floor |

Expected values based on simulated scenario. Actual results may change. AI predictions are based on current configuration, safety checks, and passed activation scenarios.

View technical validation

### Recommended before activation

Three required activation scenarios are already passed: normal execution, safety blocking, and recovery.

| | | |
|---|---|---|
| Normal execution | Current site conditions | Passed |
| Safety blocking | High battery temperature | Passed |
| Recovery | Battery unavailable | Passed |

### Configured actions

3 actions

**Support demand using Battery 1** Testing
7 of 7 settings complete
Test coverage 3 of 3 required
Current scenario ● Passed · 3 required scenarios

**Charge battery using surplus solar** Draft
3 of 7 settings complete

**Sell surplus electricity** Connection required
Electricity market not connected